



SECTION 09 50 00 – Silentia Dimensional Concave Panels (Metal+Felt)

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Acoustical ceiling panels
 - 2. Suspension systems
 - 3. Accessories: provide other necessary items including devices for attachment overhead construction, secondary members, connecting clips, wall connectors, wall angles, and other devices required for a complete installation.
 - 4. Supplemental support framing: Provide fully engineered secondary framing as required to meet code, conforming to layout shown in drawings, to support direct-hung metal ceilings suspension system.

- B. Related Sections:
 - 1. Section 09 51 00 – Acoustical Ceilings
 - 2. Section 09 53 00 – Acoustical Ceiling Suspension Assemblies
 - 3. Section 09 54 33 – Decorative Panel Ceilings
 - 4. Section 09 84 36 - Sound-Absorbing Ceiling Units
 - 5. Section 09 51 10 - Suspended Acoustical Ceilings: Conventional grid-supported acoustic ceilings
 - 6. Sections 05 40 00 – Cold-Formed Metal Framing
 - 7. Sections 09 90 00 – Paintings and Coatings
 - 8. Division 23 – Heating, Ventilating and Air Conditioning
 - 9. Division 26 – Electrical

- C. Alternatives
 - 1. Prior Approval: Unless otherwise provided for in the Contract documents, proposed product substitutions may be submitted no later than TEN (10) working days prior to the date established for receipt of bids. Acceptability of a proposed substitution is contingent upon the Architect's review of the proposal for acceptability and approved products will be set forth by the Addenda. If included in a Bid are substitute products that have not been approved by Addenda, the specified products shall be provided without additional compensation.
 - 2. Submittals that do not provide adequate data for the product evaluation will not be considered. The proposed substitution must meet all requirements of this section, including but not necessarily limited to, the following: Single source materials suppliers (if specified in Section 1.5); Underwriters' Laboratories Classified Acoustical performance; Component design, size, composition, color, and finish; Suspension system component profiles and sizes; Compliance with the referenced standards.

MAXXIT

1.3 REFERENCES

- A. American Society for Testing and Materials (ASTM)
 - 1. E 84 – "Standard Test Method for Surface Burning Characteristics of Building Materials"
 - 2. E 488 – "Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements"
 - 3. B 209 – "Standard Specification for Aluminum and Aluminum Alloy Sheet and Plate"
 - 4. C 423 – "Sound Absorption and Sound Absorption Coefficients by Reverberation Room Method"
 - 5. E 580 – "Standard Practice for Application of Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels in Areas Requiring Moderate Seismic Restraint"
 - 6. C 635 – "Standard Specification for Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings"
 - 7. C 636 – "Recommended Practice for Installation of Metal Ceiling Suspensions Systems for Acoustical and Lay-in Panels"
 - 8. A 641 – "Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire"
 - 9. A 653 – "Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy Coated (Galvannealed) by the Hot-Dip process"
 - 10. E 1264 – "Classification for Acoustical Ceiling Products"
 - 11. System Description:
 - a. Wall to Wall Configurations

1.4 SUBMITTALS

- A. Product Data: Manufacturer's published literature, including specifications.
- B. Product Certification: Manufacturer's certifications that products comply with specified requirements and governing codes including product data, laboratory test reports and research reports showing compliance with specified standards.
- C. Shop Drawings: Layout and details of acoustical ceilings show locations of items that are to be coordinated with or supported by the ceilings.
- D. Samples for Verification: Full-size units (or as specified below) of each type of ceiling assembly indicated; in sets for each color, texture, and pattern specified, showing the full range of variations expected in these characteristics. Submit samples for each type specified.
 - 1. 6" long metal panel
 - 2. 6" long felt panel
 - 3. 6" long samples of each suspension component.

1.5 INFORMATIONAL SUBMITTALS.

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
 - 1. Lighting fixtures.
 - 2. Air outlets and inlets.
 - 3. Speakers.
 - 4. Sprinklers.



- B. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Manufacturer/Installer Qualifications:
 - 1. Provide metal and felt ceiling system components produced by a single manufacturer with experience in actual production of specified products and with resources to provide consistent quality in appearance and physical properties, without delaying the work.
 - 2. Provide suspension system components produced by a single manufacturer to provide compatible components for a complete metal ceiling system installation.
 - 3. Perform installations using a firm with installers having no less than 3 years of successful experience on projects of similar size and requirements.
- B. Regulatory Requirements:
 - 1. Fire Rating Performance Characteristics: Install system to provide a flame spread of 0 - 25, complying with certified testing to ASTM E 84.
 - 2. Structural Criteria: Install and certify system to comply with structural and wind load requirements of governing codes.
 - 3. Installation Standard for Suspension System: Comply with ASTM C 636.
- C. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
 - 1. Build mockup of typical ceiling area as shown on Drawings.
 - 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.
- D. Pre-installation Conference: Conduct a conference, prior to start of installation, to review system requirements, shop drawings, and all coordination needs.

1.7 DELIVERY, STORAGE AND HANDLING

- A. Deliver system components in manufacturer's original unopened packages, clearly labeled.
- B. Store components in fully enclosed dry space. Carefully place on skids, to prevent damage from moisture and other construction activities.
- C. Handle components to prevent damage to surfaces and edges, and to prevent distortion and other physical damage.

1.8 PROJECT CONDITIONS

- A. Begin system installations only after spaces are enclosed and weather-tight, and after all wet work and overhead work have been completed.
- B. Prior to starting installations, allow materials to reach ambient room temperature and humidity intended to be maintained for occupancy.

MAXXIT

1.9 WARRANTY

- A. Provide specified manufacturer's warranty against defects in workmanship, discoloration, or other defect considered undesirable by the Architect or Employer.
- B. This warranty shall remain in effect for a minimum period of one (1) year from date of initial acceptance.

1.10 MAINTENANCE & EXTRA MATERIALS

- A. Maintenance Instructions: Provide manufacturer's standard maintenance and cleaning instructions for finishes provided.
- B. Extra Materials: Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents. Only typical system components are included with attic stock.
 - 1. Acoustical Metal and Felt Ceiling Panels: Full-size units equal to two percent (2%) of amount installed.
 - 2. Ceiling Suspension System Components: Quantity of each grid and exposed component equal to two percent (2%) of amount installed.

1.11 LEED

- A. Maxxit Metal Ceilings qualify for the following credits:
 - 1. Category - Material & Resources
 - a. MR Credit 2.1, 2.2 - Construction Waste Management Divert 50% or 75% from disposal
 - b. MR Credit 4.1, 4.2 - Recycled Content
 - c. MR Credit 5.1, 5.2 - Regional Materials (dependent on location)
 - 2. LEED NC - 10% Extracted, Processed & Manufactured Regionally
 - 3. LEED CI - 20% Manufactured Regionally
 - a. Category - Indoor Environmental Quality
 - 1) EQ Credit 4.1 to 4.6 - Low-Emitting Materials
 - b. Category - Innovation and Design Process
 - 1) ID Credit - Acoustic Performance

PART 2 - PRODUCTS

2.1 MANUFACTURER

- A. Silentia Dimensional Concave panels manufactured by Maxxit Ceilings & Walls: 1000 Martin Grove Rd, Toronto, ON M9W 4V8. Phone 905-206-9349.
- B. Substitutions not permitted.

MAXXIT

2.2 SYSTEM MATERIALS

- A. Silentia Dimensional Concave panels for interior installations providing standard T-bar grid suspension systems. Material thickness per manufacturer's recommendations.
- B. Panel Profiles – Aluminum sheet, mechanically formed; Thermoformed PET acoustic felt.
- C. Dimensions
 - 1. Standard:
 - a. 1' x 2'
 - b. 2' x 2'
- D. Concave Ceiling Panels
 - 1. Ceiling Panel Type – Concave ceiling panels
 - 2. Color: 'Standard', 'Color Matched'
 - 3. Size: Beam - Width, Length
 - 4. Noise Reduction Coefficient (NRC): up to 0.85
 - 5. Flame Spread: ASTM E 1264; Class A (HPVA).
 - 6. Recycle Content: Pre-Consumer – up to 60% felt, up to 80% aluminum
 - 7. Acceptable Product: Silentia Dimensional Concave Panels manufactured by Maxxit
- E. Suspension:
 - 1. Panels can be suspended from 15/16" Grid
 - a. Grid features a 15/16" face width and surface painted cap that is widely used in interior designs today. Contains G30 galvanized steel with load carrying capacity of intermediate duty per ASTM C635.
 - b. Finish: (Black)(White)(Other: _____)
- F. Perforations available on painted finish options only:
 - 1. Non-Perforated
- G. Panel Finish:
 - 1. Paint; color to be selected by architect
 - a. Applied Polyester Powder Coat
 - 2. Felt

2.3 ACCESSORY MATERIALS

- A. Ell Brackets: mounting bracket
- B. Torsion springs
- C. Trim

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and structural framing to which metal panels attach or abut, with installer

MAXXIT

present, for compliance with requirements specified in this and other Sections that affect installation and anchorage, and other conditions affecting performance of metal panel ceilings.

- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Coordination: Furnish layouts for cast-in-place anchors, clips, and other ceiling anchors whose installation is specified in other Sections.
- B. Measure each ceiling area and establish layout of acoustical metal pan units to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width units at borders and comply with layout shown on reflected ceiling plans.
- C. Survey substrate for wall attachment to assure squareness and proper elevation for wall panel installation.

3.3 INSTALLATION

A. General: Install metal panel ceilings, per manufacturers shop drawings provided, per manufacturer's written instructions and to comply with publications referenced below.

1. CISCA "Ceiling Systems Handbook"
2. Standard for Ceiling Suspension System Installations - ASTM C 636
3. Standard for Ceiling Suspension Systems Requiring Seismic Restraint - ASTM E 580
4. IBC (International Building Code) Standard for Seismic Zone for local area

B. Suspend ceiling hangers from building's approved structural substrates and as follows:

1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, counter-splaying, or other equally effective means.
3. Where width of ducts and other construction within ceiling plenum produce hanger spacings that interfere with location of hangers at spacing required to support standard suspension system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices. Utilize supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.
4. Where used secure wire hangers to ceiling suspension members and to supports above

MAXXIT

with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure; that are appropriate for substrate; and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.

5. Space hangers not more than 48" on-center, along each member supported directly from hangers, unless otherwise indicated; and provide hangers not more than 12" from ends of each member.
 6. Level grid to 1/8" in 10' from specified elevation(s), square and true.
 7. Adjust suspension system runners so they are square (within .5 degree from 90 degrees) and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- C. Secure bracing wires to ceiling suspension members and to supports acceptable to Architect/Engineer and/or inspector. Suspend bracing from building's structural members and/or structural deck, as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs (unless directed otherwise).
- D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical metal pan. Method of edge trim attachment and design of edge trims to be approved by Architect.
- E. Scribe and cut metal panel units for accurate fit at penetrations by other work through ceilings. Stiffen edges of cut units as required to eliminate evidence of buckling or variations in flatness exceeding referenced standards for stretcher-leveled metal sheet.
- F. Install metal panel units in coordination with suspension system.
1. Align joints in adjacent courses to form uniform, straight joints parallel to room axis in both directions, unless otherwise indicated. Install directionally patterned or textured panels in directions indicated on approved shop drawings. Panel- joints shall flow smoothly and in a straight line within 1/8" in 10'. Intersections shall be continuous.
 2. Fit adjoining units to form flush, tight joints. Scribe and cut units for accurate fit at borders and around construction penetrating ceiling.
 3. When required by the jobsite, remove protective film from panels only when space is completely clean and free of airborne particles. Use white cotton gloves for final installation of panels into grid system.

3.4 ADJUST AND CLEAN

- A. Adjust components to provide uniform tolerances.
- B. Replace all ceiling components that are scratched, dented or otherwise damaged.
- C. Clean exposed surfaces with non-solvent, non-abrasive commercial type cleaner.

MAXXIT

3.5 CLEANING

A. Clean exposed surfaces of suspended decorative grids, including trim and edge moldings, after removing strippable, temporary protective covering if any. Comply with manufacturer's written instructions for stripping of temporary protective covering, cleaning, and touchup of minor finish damage. Remove and replace grid components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage, including dented and deformed grids.

END OF SECTION 09 50 00